

**Pennsylvania Department of Transportation – Engineering District 8-0
SR 3036 (Franklin Road) over Strickler Run
West Hempfield Township, Lancaster County**

Project Description

The SR 3036, Section 005 bridge preservation project is located along SR 3036 (Franklin Road) over Strickler Run in West Hempfield Township, Lancaster County. The purpose of this project is to extend the life of the bridge and provide continued access on SR 3036, Section 005 (Franklin Road) over Strickler Run.

The primary focus of the preservation project is to repair the reinforced concrete deck and to remediate the existing scour along the abutments. The top of deck will first be scarified and a 1¼” thick latex modified concrete (LMC) overlay will be installed on top. Rock will be placed along both abutments and along the channel at the far-left bridge corner and channel migration areas in order to mitigate the existing scour and prevent future scour from occurring. Please refer to the project’s preliminary plan graphic.

Environmental Considerations

The bridge is located in a rural residential area of West Hempfield Township, with land use largely consisting of residential parcels. Pedestrian or bicycle facilities do not exist through this section of SR 3036.

In-stream work will be limited and include the placement of scour protection.

There are no wetlands in the project area.

Utilities

Overhead electric and data/communication lines and poles are present at the site. Utility relocations are currently not anticipated to accommodate construction operations.

Maintenance and Protection of Traffic

The bridge will be closed for approximately 2-3 weeks to all traffic during construction. The potential 4.7-mile detour will utilize PA Route 462 and SR 3017 (Central Manor Road). Please refer to the project’s Detour Plan graphic. Access to all driveways within the project limits will be maintained during construction.

Construction Schedule and Cost

Construction is anticipated to begin in Spring 2027 and last approximately 2 months. The estimated construction cost is \$242,130.

Contact

If there are any questions or concerns related to the project, please contact Diane Crispino, Project Manager, at (717) 540-6040 or email c-dcrispin@pa.gov.

SR 3036-005 over Strickler Run – West Hempfield Township, Lancaster County (MPMS No. 101290)