OS-299	(10-22)



TRANSMITTAL LETTER

PUBLICATION:
148
DATE:

6/20/2023

SUBJECT:

Revisions to Traffic Standards – Signals TC-8800 Series December 2011 Edition, Change No. 1

INFORMATION AND SPECIAL INSTRUCTIONS:

Incorporate the attached revisions to the December 2011 Edition of Publication 148.

These revised Standard Drawings should be adopted on all new and existing designs as soon as possible without affecting any letting schedules and in conjunction with current Publication 408 Specifications. Regardless, revised standards under this release must be used on all projects let after October 6, 2023.

Throughout the entire document these standards were updated to include revised Publication 408 Specification references contained in the traffic signal specification updates per Change No. 3 of the Publication 408/2020 update.

Additions, deletions, and revisions specific to each Standard and Sheet are as follows:

STANDARD	SHEET	DESCRIPTION OF CHANGES	
TC-8801	1	Updated Mast Arm Details as follows: -Revised Handhole callout leader location on Plan View of mast arm to match location of handhole depicted in Elevation View -Revised bolt pattern on Elevation View of mast arm pole base plate. Bolts depicted now represent six bolt pattern implemented in 2011 TC-8801 updates. Updated Notes as follows:	
		 Revised Note 7 from "ARMS LESS THAN 31' WILL BE ONE SECTION" to "ARMS 30' OR LESS WILL BE ONE SECTION Revised second sentence of Note 16 from "PROVIDE GALLOPING MITIGATION DEVICE IN ACCORDANCE WITH PUB 408, SECTION 1104.02(b) IF THE MAXIMUM DISPLACEMENT (MAX. POSITIVE TO MAX. NEGATIVE) ATHE MAST ARM TIP EXCEEDS 8"." to "PROVIDE GALLOPING MITIGATION DEVICE IN ACCORDANCE WITH MITIGATION DEVICE DETAIL ON SHEET 10 IF THE MAXIMUM DISPLACEMENT (MAX. POSITIVE TO MAX. NEGATIVE) AT THE MAST ARM TIP EXCEEDS 8"." 	
TC-8801	2	Updated Strain Pole Details as follows:	

TC-8801	3	-Revised bolt pattern on Elevation View of strain pole base plates. Bolts depicted now represent six bolt pattern implemented in 2011 TC-8801 updates. Updated Foundation Notes as follows: Revised Note 7 from "GALVANIZE ALL STRUCTURAL STEEL IN ACCORDANCE WITH PUB. 408, SECTION
		 1104.02(a) 8." to "GALVANIZE ALL STRUCTURAL STEEL IN ACCORDANCE WITH PUB. 408, SECTION 951.2(c)1.d" Revised Note 10 from "USE STEEL TEMPLATE TO SET ANCHOR BOLTS IN ACCORDANCE WITH PUBLICATION 408, SECTION 1104.02 (e)." to "USE STEEL TEMPLATE TO SET ANCHOR BOLTS IN ACCORDANCE WITH PUBLICATION 408, SECTION 951.2(c)5."
TC-8801	4	Updated Type A Foundation Case 1 Section F-F Detail as follows:
		-Removed "(SEE NOTE 5)" from "GALVANIZED WIRE MESH OR GROUT" callout .
		Updated Notes as follows:
		 Revised the first sentence of Note 3 from "IN A PAVED AREA, PLACE THE TOP OF FOUNDATION FLUSH WITH THE SURFACE OF THE ADJACENT PAVEMENT" to "IN A SIDEWALK AND PAVED AREA, PLACE THE TOP OF FOUNDATION FLUSH WITH THE SURFACE OF THE ADJACENT PAVEMENT" Removed Note 5 Renumbered Notes 6, 7, and 8 to Notes 5, 6, and 7 respectively
TC-8801	8	Updated Type B Foundation Section G-G Detail as follows:
		-Removed "(SEE NOTE 7)" from "GALVANIZED WIRE MESH OR GROUT" callout .
		Updated Notes as follows:
		 Revised the first sentence of Note 3 from "IN A PAVED AREA, PLACE THE TOP OF FOUNDATION FLUSH WITH THE SURFACE OF THE ADJACENT PAVEMENT" to "IN A SIDEWALK AND PAVED AREA, PLACE THE TOP OF FOUNDATION FLUSH WITH THE SURFACE OF THE ADJACENT PAVEMENT" Removed Note 7 Renumbered Note 8 to Note 7
TC-8801	9	Updated Sign Bracket – Mast Arm Detail as follows:
		-Revised "STAINLESS STEEL BAND CONFORMING TO PUBLICATION 408, SECTION 1103.11(n)." callout to "STAINLESS

Г	T		
		STEEL BAND CONFORMING TO PUBLICATION 408, SECTION 1103.11(k).".	
		Updated Notes as follows:	
		 Revised Note 4 from "ALUMINUM SIGN BOLTS, NUTS, WASHERS AND NYLON WASHERS SHALL CONFORM TO PUBLICATION 408, SECTION 1103.11 (m), SECTION 1103.11 (n), SECTION 1103.11 (o) 1 AND SECTION 1103.11 (o) 2 RESPECTIVELY." to "ALUMINUM SIGN BOLTS, NUTS, WASHERS AND NYLON WASHERS SHALL CONFORM TO PUBLICATION 408, SECTION 1103.11." Revised Note 5 from "GALVANIZED STEEL U-BOLTS, NUTS AND LOCK WASHERS SHALL BE CONFORM TO PUBLICATION 408, SECTION 1105.02 (c) 1, AND SHALL BE OF 1/4" X 3" X 1 7/8"." to "GALVANIZED STEEL U-BOLTS, NUTS AND LOCK WASHERS SHALL CONFORM TO PUBLICATION 408, SECTION 1105.02 (c) 1, AND SHALL BE OF 1/4" X 3" X 1 7/8"." 	
TC-8802	1	Updated Controller Assembly on Traffic Signal Support Type II Mounting Detail as follows:	
		-Depicted bolt pattern on Elevation View of signal pole base plates. Bolts depicted represent six bolt pattern implemented in 2011 TC- 8801	
TC-8803	1	Updated Traffic Signal Support – Pedestal Plate Base Detail as follows:	
		-Depicted bolt pattern on Elevation View pedestal base plate.	
		Updated Pedestrian Pushbutton Vertical Placement Detail as follows:	
		-Depicted bolt pattern on Elevation View of signal pole base plate. Bolts depicted represent six bolt pattern implemented in 2011 TC-8801	
		Updated Notes as follows:	
		Revised the last sentence of Note 5 from "SEE DETAIL C ON SHEET 9 OF TC-8801." to "SEE DETAIL C ON SHEET 10 OF TC-8801."	
TC-8803	2	Updated Pedestrian Pushbutton Mounting Details Type B as follows:	
		-Revised "PEDESTRIAN SIGN" callout to "PUSHBUTTON SIGN.". Callout was revised to be consistent with similar callouts on Type A, Type C, and Type F Details.	
		Updated Notes as follows:	
		Revised the last sentence of Note 4 from "SEE DETAIL C ON SHEET 9 OF TC-8801." to "SEE DETAIL C ON SHEET 10 OF TC-8801."	

		 Revised last sentence of Note 7 from "EXTENSION ARMS MEASURING BETWEEN 3" TO 12" REQUIRE DISTRICT APPROVAL PRIOR TO INSTALLATION." to "EXTENSION ARMS MEASURING GREATER THAN 12" REQUIRE DISTRICT APPROVAL PRIOR TO INSTALLATION." Added Note 8 - "INSTALL CONCRETE FOUNDATIONS IN ACCORDANCE WITH PUBLICATION 408 SECTION 951.2 (b) AND 951.3 (b).".
TC-8803	3	Updated Pedestrian Pushbutton Mounting Details Type D and Type E as follows:
		-Revised "PEDESTRIAN SIGN" callout to "PUSHBUTTON SIGN.". Callout was revised to be consistent with similar callouts on Type A, Type C, and Type F Details.
		Updated Notes as follows:
		 Revised the last sentence of Note 4 from "SEE DETAIL C ON SHEET 9 OF TC-8801." to "SEE DETAIL C ON SHEET 10 OF TC-8801." Revised last sentence of Note 7 from "EXTENSION ARMS BETWEEN 3" TO 12" REQUIRE DISTRICT APPROVAL PRIOR TO INSTALLATION." to "EXTENSION ARMS GREATER THAN 12" REQUIRE DISTRICT APPROVAL PRIOR TO INSTALLATION." Added Note 8 - "INSTALL CONCRETE FOUNDATIONS IN ACCORDANCE WITH PUBLICATION 408 SECTION 951.2 (b) AND 951.3 (b).".
TC-8804	2	Updated Junction Box, Type JB-26 and Junction Box, Type JB-27 Details as follows:
		-Revised Junction Box Details to a typical detail for cast iron or steel and a typical detail for reinforced plastic mortar or high-density polymer concrete with dimensions for each detail labeled as variables. Identified corresponding required JB-26 and JB-27 dimensions in tabular format. Added JB-30 dimensions to table as applicable.
		Updated Typical Junction Box Installation Junction Box in Paved Surface Detail as follows:
		-Revised label of detail from 'JUNCTION BOX IN PAVED SURFACE" to "JUNCTION BOX IN PAVED SURFACE AND SIDEWALK"
		Updated Trench and Backfill Detail as follows:
		-Revised fifth symbol note from "BACKFILL AS SPECIFIED IN SECTION 954, PUBLICATION 408" to "BACKFILL AS SPECIFIED IN SECTION 910.3 (c), PUBLICATION 408"
		Updated Notes as follows:
		Revised the first sentence of Note 2 from "JUNCTION BOXES – USE JB-26 AND JB-27 ONLY IN AREAS NOT SUBJECT

		TO VEHICULAR TRAFFIC." to "JUNCTION BOXES – USE JB-26, JB-27 AND JB-30 ONLY IN AREAS NOT SUBJECT TO VEHICULAR TRAFFIC"
TC-8805	1	Updated Visor Types for Vehicular Signal Head Details as follows:
		-Removed Full-Circle Visor Detail -Added Dimension B to show visor lengths in lieu of describing in a note -Added a visor dimension table for visor dimensions A and B -Revised detail note from "THE VISOR SHALL BE A MINIMUM OF 9.5" FOR A 12" SIGNAL LENS AND 7" FOR AN 8" SIGNAL LENS WITH A DOWNWARD TILT OF 3.5 DEGREES" to "THE VISOR SHALL HAVE A DOWNWARD TILT OF AT LEAST 3"
		Updated Backplate for Vehicular Signal Head Detail as follows:
		 Revised "5" MIN" callouts to "5" - 8".". Revised Backplate detail to show reflective yellow border and added callout "2" MIN. FLOURESCENT YELLOW RETROREFLECTIVE BORDER"
		- Added note below detail label which reads "*BACKPLATE CONFORMING TO PUBLICATION 408 SECTION 955.2 (B) 3 SHALL BE ONE PIECE ALUMINUM"
		Updated Pedestrian Signal Head Detail as Follows:
		-Corrected spelling of word "SHOULD" in bottom note
TC-8806	1	Updated Typical Sensor Installation – Loop Detector Section A-A Detail as follows:
		-Removed detail and replaced with a detail depicting installation of loop wire with backer rods Revised detail note from "NO MORE THAN FOUR CONDUCTORS SHALL BE PLACED IN A SLOT. FOUR CONDUCTORS SHOWN FOR ILLUSTRATION PURPOSES ONLY." to "THREE CONDUCTORS SHOWN FOR ILLUSTRATION PURPOSES ONLY."
TC-8806	2	Updated Detector Splice Alternate A Detail as follows:
		-Revised callout from "SEALANT (SEC. 1104.07 (a) 1, PUBLICATION 408)" to "SEALANT (SEC. 956.2 (b) 1, PUBLICATION 408)"
		Updated Detector Splice Alternate C Detail as follows: -Revised last line of note from "SEC. 1104.07 (a) 4, PUBLICATION 408." to "SEC. 956.2 (b) 4, PUBLICATION 408.
All		Revised "Bureau of Maintenance and Operations" to "Bureau of Operations"

CANCEL AND DESTROY THE FOLLOWING:

Publication 148 – TC-8801 SHEET 1 – Dec. 12, 2011 TC-8801 SHEET 2 – Dec. 12, 2011 TC-8801 SHEET 3 – Dec. 12, 2011 TC-8801 SHEET 4 – Dec. 12, 2011 TC-8801 SHEET 8 – Dec. 12, 2011 TC-8801 SHEET 9 – Dec. 12, 2011 TC-8802 SHEET 1 – Dec. 12, 2011 TC-8803 SHEET 1 – Dec. 12, 2011 TC-8803 SHEET 2 – Dec. 12, 2011 TC-8803 SHEET 3 – Dec. 12, 2011 TC-8804 SHEET 2 – Dec. 12, 2011 TC-8805 SHEET 1 – Dec. 12, 2011 TC-8806 SHEET 1 – Dec. 12, 2011 TC-8806 SHEET 2 – Dec. 12, 2011

NOTE: Publication 148 is only available electronically via the PennDOT website

ADDITIONAL COPIES ARE AVAILABLE FROM:

PennDOT website - www.penndot.pa.gov Click on Forms, Publications & Maps

APPROVED FOR ISSUANCE BY:

Daniel P. Farley, P.E. /s/ Director, Bureau of Operations

OS-299	(7-08)
05-299	(7-08)



TRANSMITTAL LETTER

	101	TO		\sim		
u	1141	_ICA	\ I I	4 N	N	•
гι	JUL	_1 \	ν і т	v	N	

148

DATE:

12/12/2011

SUBJECT:

Traffic Standards - Signals (TC-8800 Series)

INFORMATION AND SPECIAL INSTRUCTIONS:

Project Development:

The accompanying revisions become effective December 21, 2011 or earlier as directed by the District Executive, for all projects with traffic signal supports as follows:

- All Department projects that have not submitted Plans, Specifications, and Estimate packages prior to effective date.
- All Highway Occupancy Permits or Municipal projects that do not have an approved Traffic Signal Permit prior to the effective date.

Shop Drawing Review:

In addition to the revisions made to the standards, , Publication 35, Bulletin 15 (Approved Construction Materials) Section 1104.02, will also be updated accordingly to indicate those manufacturers who have been recertified to provide traffic signal supports meeting the new criteria. Drawings for the approved manufacturers are available for Department representatives for reviewing and approving shop drawings. The approved manufacturer drawings are available at: ftp://ftp.dot.state.pa.us/transfer/Traffic Signals/Traffic Signal Structrual Supports/.

Maintenance:

If a traffic signal structural support needs to be replaced due to knockdown, the Department will allow the traffic signal structural support to be reinstalled using the standard in place at the time of initial installation. If the foundation needs to be modified or replaced as part of a knockdown, then the 2011 updated standard should be followed.

CANCEL AND DESTROY THE FOLLOWING:

This will replace the 10/14/2010 Publication 148 (Traffic Standards - Signals (TC-8800 Series)

ADDITIONAL COPIES ARE AVAILABLE FROM:

- PennDOT SALES STORE
 (717) 787-6746 phone
 (717) 787-8779 fax
 ra-penndotsalesstore@state.pa.us
- PennDOT website www.dot.state.pa.us

 Click on Forms, Publications & Maps
- ☐ DGS warehouse (PennDOT employees ONLY)

APPROVED FOR ISSUANCE BY:

Daryl St. Clair, P.E. /s

The following are changes from the October 14, 2010 update:

Traffic Control		
Standard #	Sheet #	Description of the Change
TC-8800 Series		All of the sheets have been updated to reflect the PennDOT reogranization which is expected in the upcoming weeks.
TC-8801	Sheet 1	An additional general note has been added to indicated that a mitigation device should be placed on sign mast arms over 50-feet.
TC-8801	Sheet 1	An additional general note has been added to indicate the limitations of a dual mast arm installation.
TC-8801	Sheet 3	The anchor bolt lengths have been modified to reflect appropriate design lengths instead of a 6-foot anchor bolt for all situations.
TC-8801	Sheet 3	The foundation design criteria has been modified addressing concerns that the previous traffic signal foundations were too conservative.
TC-8801	Sheet 3	Traffic signal pedestal supports are permitted to have a 4-anchor bolt configuration. The Traffic Signal Support Mast Arm and Strain Pole will still require 6-anchor bolts for new installations.
TC-8801	Sheet 3	Three additional rock cases have been added and are more clearly defined on sheet 4.
TC-8801	Sheet 3	An additional foundation note has been added providing instructions if weak soil conditions are encountered.
TC-8801	Sheet 4	An additional Note has been added referencing the additional pedestrian pushbutton details in TC-8803.
TC-8801	Sheet 4	An additional note indicating the Alternate Type A foundation details has been added.
TC-8801	Sheet 4	The foundation depths and associated notes are provided on Sheets 5 and 6.
TC-8801	Sheet 4	Three additional Rock cases have been added to provide alternative foundation depths when rock is encountered.
TC-8801	Sheet 4	The closed tie detail has been updated to eliminate the hooks.
TC-8801	Sheet 5	All of the Mast Arm and Pedestal Foundation Type A depths are indicated for all of the standard cases.
TC-8801	Sheet 6	All of the Strain Pole Foundation Type A depths are indicated for all of the standard cases.
TC-8801	Sheet 7	A new sheet has been added addressing an alternative reduced foundation diameter. The Bureau of Maintenance and Operations approval would be required to use this foundation alternative.
TC-8801	Sheet 9	The aluminum Z dimensions have been updated.
TC-8801	Sheet 9	The galvanized steel U-bolt nuts and lock washers dimensions contained within Note 5 have been updated.
TC-8801	Sheet 10	The handhole detail has been updated.
TC-8801	Sheet 10	A mitigation device detail has been added.
TC-8803	Sheet 1	An additional Note referencing the pedestrian pushbutton mounting details has been added.
TC-8803	Sheet 1	The pedestrian push button height requirements have been updated.
TC-8803	Sheet 2 and 3	Two additional sheets with 6 types of pedestrian pushbutton pole installation details have been added.
TC-8803	Sheet 2 and 3	An additional Note defining the pedestrian pushbutton extension requirements has been added.

12/12/2011

COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION

TRAFFIC STANDARDS—SIGNALS TC-8800 SERIES

BUREAU OF OPERATIONS


DECEMBER 2011 EDITION



INDEX OF TRAFFIC STANDARDS - SIGNALS


STANDARD	DRAWING NO.	DATE	DESCRIPTION
TC-8801	(10 SHEETS)	JUN 20, 2023*	TRAFFIC SIGNAL SUPPORT
TC-8802		JUN 20, 2023*	CONTROLLER ASSEMBLY
TC-8803	(4 SHEETS)	JUN 20, 2023*	MISCELLANEOUS
TC-8804	(2 SHEETS)	JUN 20, 2023*	ELECTRICAL DISTRIBUTION
TC-8805		JUN 20, 2023*	SIGNAL HEADS
TC-8806	(2 SHEETS)	JUN 20, 2023*	DETECTORS

* SEE CHANGE #1 FOR JUNE 20, 2023 STANDARD REVISIONS



MINIMUM BREAKING STRENGTH OF SPAN WIRE

NOM. DIA. OF SPAN WIRE	ASTM A 475, CLASS A, SIEMENS-MARTIN GRADE	ASTM B 416
1/4 "	3150 lbs	6301 lbs
5/16 "	5350 lbs	10,020 lbs
3/8 "	6950 lbs	15,930 lbs
7∕16 "	9350 lbs	19,060 lbs
1/2 "	12,100 lbs	23,000 lbs



GENERAL NOTES:

CABLE SUPPORT

CABLE '

(ALTERNATE METHOD TO PROVIDE LUMINAIRE)
(SEE NOTES 11 AND 12)

SPAN WIRE CLAMP (SEE NOTE 10)

STRAIN POLE

CABLE ENTRANCE 4"Ø (MIN.)

DISTRIBUTION CABLE

CLAMP SUITABLE FOR ANY COMBINATION OF COPPER, ALUMINUM OR STEEL CONDUCTORS (TYP.)

DEAD-END, FEED-THRU STRANDVISE WITH STAINLESS STEEL BAIL

(SEE NOTE 5)-

- 1. FOR FOUNDATION DETAILS, SEE SHEETS 3 THROUGH 7.
- 2. INSTALL A MINIMUM OF ONE GROUND ROD AT EACH FOUNDATION, SEE TC-8804, SHT.1.
- DIMENSION "K" IS FROM SIDEWALK. IF NO SIDEWALK, DIMENSION "K" IS FROM PAVEMENT GRADE AT CENTER OF ROADWAY. PROVIDE SPECIFIED DIMENSION "K" SUCH THAT CLEARANCE IS IN THE RANGE OF: 8' MINIMUM, 15' MAXIMUM FOR TRAFFIC SIGNAL HEADS; MINIMUM, 10' MAXIMUM FOR PEDESTRIAN
- 4. DIMENSION "F" IS 2' MINIMUM FROM CURB OR FROM EDGE OF SHOULDER. PLACE POST-MOUNTED SIGNALS 2' MINIMUM BEHIND CURB OR EDGE OF SHOULDER.
- LASH DISTRIBUTION CABLE TO THE SPAN WIRE WITH PREFORMED GALVANIZED STEEL RODS, SELF-LOCKING
 CABLE TIES OF THE OUTDOOR TYPE, SOLID COPPER WIRE,
 GALVANIZED STEEL WIRE, STAINLESS STEEL WIRE, OR
 CABLE RINGS AND SADDLES. MAKE ONE COMPLETE WRAP
 WITH WIRE LASHING AT INTERVALS NOT EXCEEDING
 6". SECURE ENDS OF WIRE LASHING TO THE SPAN WIRE WITH AN ALL PURPOSE SPLIT BOLT CONNECTOR. PLACE
 CABLE TIES AT INTERVALS NOT EXCEEDING 12". PROVIDE
 PROPER SIZE AND SPACING OF CABLE RINGS AND SADDLES
 ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
- PROVIDE DEAD-ENDS THAT DEVELOP THE STRENGTH OF THE SPAN WIRE.
- 7. FOR QUANTITY, SIZE, SIZE OF HOLES AND BOLT CIRCLE FOR ANCHOR BOLTS, SEE SHEET 3.
- 8. TETHER WIRE 1/4" DIAMETER (NOMINAL) WITH A BREAKING STRENGTH OF 1900 Ibs MEETING ASTM A 475, CLASS A, COMMON GRADE.
- PROVIDE SPECIFIED CLEARANCE IN ACCORDANCE WITH PUBLICATION 149 AND THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".
- 10. EACH SPAN OR TETHER WIRE WILL HAVE AN INDIVIDUAL SPAN WIRE CLAMP.
- USE ONE-PIECE STRAIN POLE WHEN LUMINAIRE IS REQUIRED EXCEPT FOR ROUND STEPPED SUPPORTS, OR UNLESS ALTERNATE OVERLAP SLIP JOINT IS SPECIFIED OR APPROVED ON A
- IF SPECIFIED, PROVIDE 36" MINIMUM STUB TO ALLOW FUTURE LUMINAIRE ATTACHMENT VIA OVERLAP

COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION BUREAU OF OPERATIONS

STANDARD

TRAFFIC SIGNAL SUPPORT STRAIN POLE

RECOMMENDED JUN 20, 2023	RECOMMENDED JU
CHIEF, TSMO ARTERIALS AND	CHIEF OF HIGHWAY

UN 20, 2023

SHEET 2 OF 10 SAFETY AND NS DIVISION TC-8801

ANCHOR BOLT DESIGN, MAST ARM

HIGT IDE		ONE ARM			TWO ARMS *				
MAST ARM LENGTH	QTY.	DIA.	LGTH.	в. с.	HOLE	DIA.	LGTH.	в. с.	HOLE
0 - 10'	6	1 3/4 "	35 "	18"	2 "	1 3/4 "	35 "	18"	2 "
>10' - 15'	6	1 3/4 "	35 "	18"	2 "	1 3/4 "	35 "	18"	2 "
>15' - 20'	6	1 3/4 "	35 "	18"	2 "	1 3/4 "	35 "	18"	2 "
>20' - 25'	6	1 3/4 "	35 "	18"	2 "	1 3/4 "	35 "	18"	2 "
>25' - 30'	6	1 3/4 "	35 "	21"	2 "	1 3/4 "	35 "	21"	2 "
>30' - 35'	6	1 3/4 "	35 "	21"	2 "	1 3/4 "	35 "	21"	2 "
>35' - 40'	6	2 "	40"	24"	21/4"	2 "	40"	24"	21/4"
>40' - 45'	6	2 "	40"	24"	21/4"	2 "	40"	24"	21/4"
>45' - 50'	6	2 "	40"	24"	21/4"	2 "	40"	24"	21/4"
>50' - 60'	6	2 "	40"	24"	21/4"	2 "	40"	24"	21/4"


ANCHOR BOLT DESIGN, STRAIN POLE

DESIGN	SHAFT LENGTH 20' - 24'			SHAFT LENGTH 26' - 30'			SHAFT LENGTH 32' - 34'						
TENSION (LBS)	QTY.	DIA.	LGTH.	В. С.	HOLE	DIA.	LGTH.	В. С.	HOLE	DIA.	LGTH.	в. с.	HOLE
1000	6	1 3/4 "	35 "	18"	2 "	2 "	40"	18"	21/4"	2 "	40"	18"	21/4"
2000	6	1 3/4 "	35 "	18"	2 "	2 "	40"	18"	21/4"	2 "	40"	18"	21/4"
3000	6	1 3/4 "	35 "	18"	2 "	2 "	40"	18"	21/4"	2 "	40"	18"	21/4"
4000	6	1 3/4 "	35 "	18"	2 "	2 "	40"	18"	21/4"	2 "	40"	18"	21/4"
5000	6	1 3/4 "	35 "	18"	2 "	2 "	40"	18"	21/4"	2 "	40"	18"	21/4"
6000	6	21/4"	45 "	18"	21/2"	21/4"	45 "	21"	21/2"	21/4"	45 "	21"	21/2"
7000	6	21/4"	45 "	18"	2 1/2 "	21/4"	45 "	21"	21/2"	21/4"	45 "	21"	21/2"
8000	6	21/4"	45 "	18"	21/2"	21/4"	45 "	21"	21/2"	21/4"	45 "	21"	21/2"
9000	6	21/4"	45 "	18"	21/2"	21/4"	45 "	21"	21/2"	21/2"	45 "	21"	2 3/4 "
10,000	6	21/4"	45 "	18"	21/2"	21/4"	45 "	21"	21/2"	21/2"	45 "	21"	2 3/4 "


* TWO ARMS PERPENDICULAR TO EACH OTHER. ADDITIONAL STRUCTURAL ANALYSIS IS REQUIRED FOR TWO MAST ARMS AT ACUTE OR OBTUSE ANGLES TO EACH OTHER B.C. = BOLT CIRCLE DIAMETER

ANCHOR BOLT DESIGN, PEDESTAL POLE


PEDESTAL SHAFT	ANCHOR BOLTS					
LENGTH	QTY.	DIA.	LENGTH			
7' - 10'	4	3/4"	2'-0"			
>10' - 14'	4	3/4"	2'-0"			







ANCHOR RING DETAIL (N. T. S.)



HOLE FOR ANCHOR BOLT (TYP.)


- CIRCULAR PEDESTAL

- SQUARE PEDESTAL

BOLT CIRCLE

POLE TRAFFIC SIGNAL SUPPORTS.

BASE MOUNT PLAN NOTE: A MINIMUM OF 6 ANCHOR BOLTS IS REQUIRED FOR MAST ARM AND STRAIN



ANCHOR RING DETAIL (N.T.S.)

TRAFFIC SIGNAL SUPPORT
MAST ARM AND STRAIN POLE
ANCHOR BOLT DETAILS

DESIGN CRITERIA

(SEE NOTE 13)

ALL MAIN LOAD CARRYING TENSION MEMBERS GREATER THAN $\frac{1}{2}$ INCH THICKNESS MUST MEET AASHTO ZONE 2, NON-FRACTURE CRITICAL MEMBER COMPONENTS (FCM) CHARPY V-NOTCH (CVN).

EXTERNAL LOADS

AASHTO SIGN SPEC T

SECTION 3.7 APPENDIX C, SECTION C.3, EQ. C-1, WITH 80 MPH WIND AND 30% GUST FACTOR

GROUP LOADS

AASHTO SIGN SPEC SECTION 3.4 T

BOLT CRITERIA

AASHTO SIGN SPEC ^T

BOLT CRITERIA ALLOWABLE ANCHOR BOLT STRESSES

SECTION 5.16 SECTION 5.17

SPREAD FOOTINGS

MAXIMUM DESIGN PRESSURE MINIMUM AREA IN BEARING UNIT WEIGHT OF SOIL

1.5 TONS PER SQUARE FOOT 100 POUNDS PER CUBIC FOOT

DRILLED SHAFTS (CAISSONS)

PENNDOT DM4 APPENDIX J, PENNDOT COM624 COMPUTER PROGRAM, OR L-PILE

CASE 1 (SOIL) MAXIMUM DESIGN PRESSURE
MAXIMUM DESIGN LATERAL DISPLACEMENT
MODULUS OF SUBGRADE REACTION:

1.5 TONS PER SQUARE FOOT 1.0"

COHESTON:

ABOVE WATER TABLE BELOW WATER TABLE WATER TABLE UNIT WEIGHT OF SOIL ANGLE OF INTERNAL FRICTION

15 POUNDS PER SQUARE FOOT 0 POUNDS PER SQUARE FOOT 5 FEET BELOW GRADE 120 POUNDS PER CUBIC FOOT 30*

CASES 2 THROUGH 4 (ROCK)

1.5 TONS PER SQUARE FOOT 1.0" MAXIMUM DESIGN PRESSURE
MAXIMUM DESIGN LATERAL DISPLACEMENT

SOIL PARAMETERS ABOVE TOP OF ROCK: MODULUS OF SUBGRADE REACTION: ABOVE WATER TABLE BELOW WATER TABLE

K = 80.0 POUNDS PER CUBIC INCH K = 60.0 POUNDS PER CUBIC INCH O POUNDS PER SQUARE FOOT 5 FEET BELOW GRADE 120 POUNDS PER CUBIC FOOT

COHESION
WATER TABLE
UNIT WEIGHT OF SOIL
ANGLE OF INTERNAL FRICTION

120 POUNDS PER CUBIC FOOT 250 POUNDS PER SQUARE INCH

ROCK PARAMETERS: UNIT WEIGHT OF ROCK UNIAXIAL COMPRESSIVE STRENGTH

FOR ROCK CASE DEFINITION, SEE ROCK SOCKET NOTES ON SHEET 4.

† LEGEND:

U. N. O.:


AASHTO SIGN SPEC:

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, "STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES AND TRAFFIC SIGNALS", 4TH EDITION (2001) INCLUDING INTERIM SPECIFICATIONS (2002, 2003 AND 2006)

UNLESS NOTED OTHERWISE

FOUNDATION NOTES:

- 1. PROVIDE 3" CONCRETE COVER ON REINFORCEMENT BARS. EXCEPT AS NOTED.
- USE CLASS A CEMENT CONCRETE $f' \circ = 3000 \; \text{PSI}$ IN PEDESTALS, FOOTINGS AND CAISSONS.
- PROVIDE GRADE 60 REINFORCING STEEL BARS THAT MEET THE REQUIREMENTS OF ASTM A615/A615M-96A FOR CONCRETE REINFORCEMENT. DO NOT WELD REINFORCING STEEL BARS.
- 4. RAKE-FINISH ALL HORIZONTAL CONSTRUCTION JOINTS, EXCEPT AS INDICATED.
- 5. CHAMFER EXPOSED CONCRETE EDGES 1" x 1".
- 6. DIMENSIONS ARE BASED ON A NORMAL TEMPERATURE OF 68°F.
- GALVANIZE ALL STRUCTURAL STEEL IN ACCORDANCE WITH PUB. 408, SECTION 951.2(c) 1.d.
- 8. PROVIDE ANCHOR BOLT HOLES 1/4 " LARGER THAN BOLT DIAMETER.
- PROVIDE ANCHOR BOLTS CONFORMING TO ASTM F1554 GRADE 55 PER PUBLICATION 408, SECTION 1105.02 (c) 3.
- 10. USE STEEL TEMPLATE TO SET ANCHOR BOLTS IN ACCORDANCE WITH PUBLICATION 408, SECTION 951.2(c) 5.
- 11. STEEL TEMPLATE TO BE PROVIDED BY MAST ARM OR STRAIN POLE FABRICATOR.
- 12. PROVIDE ANCHOR BOLTS WITH THREADS WHICH EXTEND A MINIMUM OF 3" BELOW THE TOP OF THE FOUNDATION.
- 13. SEE PENNDOT PUBLICATION 149 "CRITERIA FOR THE DESIGN OF TRAFFIC SIGNAL SUPPORTS".
- 14. IF WEAK SOIL CONDITIONS ARE ENCOUNTERED DURING CAISSON DRILLING OPERATION (I.E. SOIL MOVEMENT DURING DRILLING), NOTIFY CENTRAL OFFICE FOR APPROPRIATE FOUNDATION DEPTHS IN WEAK SOIL CONDITIONS.



LONGER ANCHOR BOLTS MAY BE REQUIRED TO AVOID CONFLICTS WITH TOP LAYER OF REINFORCEMENT IN FOUNDATION TYPE B.

ANCHOR BOLT

COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION BUREAU OF OPERATIONS


STANDARD


TRAFFIC SIGNAL SUPPORT FOUNDATION NOTES AND ANCHOR BOLT DETAILS

RECOMMENDED JUN 20, 2	RECOMMENDED JUN 20, 2023	SHEET 3 OF 10
CHIEF, JSMO ARTERIALS AND	CHIEF OF HIGHWAY SAFETY AND	TC-8801


NOTES:

- 1. PROVIDE THE TYPE "A" FOUNDATION AT ALL LOCATIONS, EXCEPT THE TYPE "B" FOUNDATION (SHOWN ON SHEET 8) MAY BE USED WHEN PHYSICAL CONDITIONS PREVENT PLACING THE TYPE "A" FOUNDATION TO ITS REQUIRED DEPTH.
- 2. FOR DESIGN CRITERIA SEE SHEET 3.
- 3. IN A SIDEWALK AND PAYED AREA, PLACE THE TOP OF FOUNDATION FLUSH WITH THE SURFACE OF THE ADJACENT PAYEMENT. GRADE ADJACENT PAYEMENT AWAY FROM ANCHOR BOLTS FOR DRAINAGE. IN UNPAYED AREAS TOP OF FOUNDATION TO BE 6" ABOVE TOP OF GROUND.
- 4. FOR GROUND ROD SIZE AND INSTALLATION DETAILS, SEE TC-8804.
- 5. FOR MAST ARM AND TRAFFIC SIGNAL PEDESTAL POLE TABLES, REFER TO SHEET 5. FOR STRAIN POLE TABLES, SEE SHEET 6.
- 6. FOR TRAFFIC SIGNAL PEDESTRIAN PUSH BUTTON POLE DETAIL, REFER TO TC-8803.
- 7. FOR MAST ARM LOCATIONS WITH SITE LIMITATIONS, ALTERNATE TYPE A FOUNDATIONS WITH SMALLER DIAMETERS MAY BE USED IF APPROVED BY THE BUREAU OF HIGHWAY SAFETY AND TRAFFIC ENGINEERING. SEE SHEET 7 FOR ALTERNATE TYPE A FOUNDATION DETAILS.






CASE 1



STIRRUP SPACING	3
COMBINATION	S1
32 FT STRAIN POLE, 10,000 LB (CASE 5)	5 "
34 FT STRAIN POLE, 10,000 LB (CASE 5)	5 "
ALL OTHER COMBINATIONS	6"

ROCK SOCKET NOTES:

- IF ROCK STRATUM IS ENCOUNTERED, USE THE TABLES PRESENTED FOR CASES 2 THROUGH 4. ROCK STRATUM IS DEFINED IN ACCORDANCE WITH PUB. 40B, SECTION 1006.1(d). FOR CASES 3 AND 4, INCREASE CAISSON DIAMETER "D" BY 6" AND INSTALL STEEL CASING TO TOP OF ROCK TO STABILIZE SOIL DURING ROCK AUGERING. STEEL CASING MAY BE PERMANENTLY LEFT IN PLACE OR REMOVED IN ACCORDANCE WITH PUB. 40B, SECTION 1006. IF A STEEL CASING IS REQUIRED FOR CASE 2, INCREASE CAISSON DIAMETER "D" BY 6".
- 2. ROCK CASES ARE DEFINED AS FOLLOWS:
 CASE 2: 0' & H1 < 5'
 CASE 3: 5' & H1 < 10'
 CASE 4: H1 \(\) 10'
- THE ROCK SOCKET DETAILS PRESENTED WITHIN THIS STANDARD ARE BASED ON ROCK PARAMETERS ON SHEET 3. ALTERNATE FOUNDATION SIZES AND TYPES MAY BE PERMITTED FOR DIFFERENT ROCK CONDITIONS PROVIDED THAT ACTUAL GEOTECHNICAL CONDITIONS ARE VALIDATED AND THE FOUNDATION DESIGN MEETS APPLICABLE CRITERIA FOR STRENGTH AND SERVICEABILITY. SUBMIT ALTERNATE FOUNDATION DESIGNS TO THE DISTRICT FOR REVIEW AND APPROVAL.
- 4. THE TOTAL CAISSON AND ROCK SOCKET DEPTH "H" NEED NOT EXCEED THE TOTAL CAISSON DEPTH "H" FOR CASE 1 UNLESS DIRECTED OTHERWISE.
- 5. FOR DETAILS NOT SHOWN, SEE TYPE A FOUNDATION DETAIL FOR CASE 1 ON THIS SHEET.



- 1/2 " CASING (PERMANENT OR TEMPORARY)

#5 BAR

26" LAP SPLICE (ALTERNATE SPLICE LOCATIONS)

"W" BAR

#5 BAR

COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION

CASES 3 AND 4

BUREAU OF OPERATIONS **STANDARD**

TRAFFIC SIGNAL SUPPORT FOUNDATION TYPE A

RECOMMENDED JUN 20, 2023	RECOMMENDED JUN 20, 2023	SHEET 4 OF 10
J&WI.C	11/	TO 0001
	CHTEF OF HIGHWAY SAFETY AND	LTC-8801
PLANNING SECTION	TRAFFIC OPERATIONS DIVISION	

MAST ARM FOUNDATION NOTES:

- 1. FOUNDATION DESIGN IS BASED ON STANDARD STRUCTURAL LOADINGS SHOWN IN THE PUBLICATION 149 AND THE FOLLOWING DESIGN ASSUMPTIONS:
- g. CENTROIDAL HEIGHT OF SIGNALS AND SIGNS ATTACHED TO THE MAST ARM AT 20' MAXIMUM FROM THE TOP OF FOUNDATION.
- b. A LUMINAIRE WITH A 15' ARM LENGTH AND A 30' MOUNTING HEIGHT FROM THE TOP OF ROADWAY.
- c. A CABINET WITH A 4'-3" HEIGHT, 2'-6" WIDTH, 1'-10" DEPTH AND A DEAD LOAD OF 281 LBS. THE CENTROIDAL HEIGHT IS LOCATED 4'-6" FROM THE TOP OF THE FOUNDATION.
- 2. WHEN THE MAST ARM SUPPORT HAS TWO ARMS WHICH ARE PERPENDICULAR TO EACH OTHER, USE THE FOUNDATION IN THE DESIGN TABLE FOR THE LENGTH OF THE LONGER ARM.
- 3. FOR DEFINITION OF CASES, SEE DRILLED SHAFT DESIGN CRITERIA ON SHEET 3 AND DETAILS ON SHEET 4.

FOUNDATION FOR TRAFFIC SIGNAL SUPPORT, MAST ARM (SOIL CONDITION)

CASE 1							
MAST ARM	"D"	H		"W"	BAR		
LENGTH			TWO ARMS*	QTY.	SIZE		
0' - 10'	3'-0"	7'-0"	7'-6"	12	#9		
>10' - 15'	3'-0"	8'-0"	8'-0"	12	#9		
>15' - 20'	3'-0"	8'-6"	9'-0"	12	#9		
>20' - 25'	3'-0"	9'-0"	9'-0"	12	#9		
>25' - 30'	3'-0"	9'-6"	10'-0"	12	#9		
>30' - 35'	3'-0"	10'-0"	10' -6"	12	#9		
>35' - 40'	3'-6"	10'-0"	10' -6"	14	#9		
>40' - 45'	3'-6"	10'-0"	11'-0"	14	#9		
>45' - 50'	3'-6"	10'-6"	11'-6"	14	#9		
>50' - 60'	3'-6"	11'-0"	12'-6"	14	#9		

^{*} TWO ARMS PERPENDICULAR TO EACH OTHER. ADDITIONAL STRUCTURAL ANALYSIS IS REQUIRED FOR TWO MAST ARMS AT ACUTE OR OBTUSE ANGLES TO EACH OTHER.

FOUNDATION FOR TRAFFIC SIGNAL SUPPORT, MAST ARM (ROCK CONDITION)

MAST ARM		CASE 2 [0'		CASE 3 [5'	∠ H1 < 10′ J	CASE 4 [H1 ≥ 10′]	w	BAR
LENGTH	"D "	H2		H2	H2 ***		***] "W" BAK	
22.101.11	**	ONE ARM	TWO ARMS*	ONE ARM	TWO ARMS*	ONE ARM	TWO ARMS*	QT	Υ.
0 - 10'	3'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	12	#9
>10' - 15'	3'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	12	#9
>15' - 20'	3'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	12	#9
>20' - 25'	3'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	12	#9
>25' - 30'	3'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	12	#9
>30' - 35'	3'-0"	4'-0"	4'-6"	4'-0"	4'-0"	4'-0"	4'-0"	12	#9
>35' - 40'	3'-6"	4'-0"	4'-6"	4'-0"	4'-0"	4'-0"	4'-0"	14	#9
>40' - 45'	3'-6"	4'-0"	4'-6"	4'-0"	4'-6"	4'-0"	4'-0"	14	#9
>45' - 50'	3'-6"	4'-0"	4'-6"	4'-0"	4'-6"	4'-0"	4'-0"	14	#9
>50' - 60'	3'-6"	4'-6"	5'-6"	4'-6"	5'-0"	4'-0"	4'-0"	14	#9

^{**} INCREASE CAISSON DIAMETER BY 6" AS APPLICABLE IN ACCORDANCE WITH ROCK SOCKET NOTE 1 ON SHEET 4.

FOUNDATION FOR TRAFFIC SIGNAL SUPPORT, PEDESTAL POLE DESIGN TABLE (SOIL CONDITION)

CASE 1							
SHAFT			"W"	BAR			
LENGTH	"D"	н	QTY.	SIZE			
7' - 10'	3'-0"	5'-0"	8	#8			
>10' - 14'	3'-0"	5'-6"	8	#8			

FOUNDATION FOR TRAFFIC SIGNAL SUPPORT, PEDESTAL POLE DESIGN TABLE (ROCK CONDITION)

	CASE 2			1 〈 5′]	
SHAFT	SHAFT "D"		"W" BAR		
LENGTH		H2	QTY.	SIZE	
7' - 10'	3'-0"	4'-0"	8	#8	
>10' - 14'	3'-0"	4'-0"	8	#8	

COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION BUREAU OF OPERATIONS

STANDARD

TRAFFIC SIGNAL SUPPORT -MAST ARM & PEDESTAL FOUNDATION TYPE A

RECOMMENDED JUN 20, 2023	RECOMMENDED JUN 20, 2023	SHEET 5 OF 10
CHIEF, (TSMO ARTERIALS AND PLANNING SECTION	CHTEF OF HIGHWAY SAFETY AND TRAFFIC OPERATIONS DIVISION	TC-8801

^{***} SEE ROCK SOCKET NOTE 4 ON SHEET 4 FOR TOTAL "H" DEPTH REQUIREMENTS.

FOUNDATION FOR TRAFFIC SIGNAL SUPPORT, STRAIN POLE (SOIL CONDITION)

		SHAFT LENGTH 20' - 34' (CASE 1)										
DESIGN	ייםיי	"W"	BAR	20' SHAFT	22' SHAFT	24' SHAFT	26' SHAFT	28' SHAFT	30' SHAFT	32' SHAFT	34' SHAFT	
TENSION				FOUNDATION								
(LBS)		QTY.	SIZE	DEPTH								
				Н	Н	Н	Н	Н	Н	Н	Н	
1000	3'-0"	12	#9	7′-6"	7′-6"	7′-6"	8'-0"	8′-0"	8'-0"	8′-6"	8′-6"	
2000	3'-0"	12	#9	8′-6"	8′-6"	8′-6"	9'-0"	9'-0"	9'-0"	9'-6"	9′-6"	
3000	3'-0"	12	#9	9'-0"	9'-0"	9'-6"	9'-6"	10′-0"	10'-0"	10′ -6"	10′ -6 "	
4000	3'-0"	12	#9	9'-6"	10'-0"	10'-0"	10' -6"	10′ -6"	11'-0"	11'-0"	11'-6"	
5000	3'-0"	12	#9	10′ -0"	10′ -6"	10' -6"	11'-0"	11'-6"	11'-6"	12′-0"	12'-0"	
6000	3'-0"	12	#9	11'-0"	11'-0"	11'-6"	12'-0"	12'-0"	12'-6"	12′ -6"	13′-0"	
7000	3'-0"	18	#9	11'-6"	11'-6"	12'-0"	12'-6"	12'-6"	13′-0"	13′ -6"	14'-0"	
8000	3'-0"	18	#9	12'-0"	12'-6"	12'-6"	13′-0"	13′-6"	14'-0"	14′ -6"	14′ -6"	
9000	3'-0"	18	#9	12'-6"	13′-0"	13′ -6"	14'-0"	14'-6"	14'-6"	15′-0"	15′-6"	
10000	3'-0"	18	#9	13′-0"	13′-6"	14'-0"	14'-6"	15′-0"	15′-0"	15′ -6"	16'-0"	

FOUNDATION FOR TRAFFIC SIGNAL SUPPORT, STRAIN POLE (ROCK CONDITION)

						CASE	2 [O' ≤ H1	< 5′]			
DESIGN	"D"	"W"	BAR	20' SHAFT	22' SHAFT	24' SHAFT	26' SHAFT	28' SHAFT	30' SHAFT	32' SHAFT	34' SHAFT
(LBS)	*	QTY.	SIZE	ROCK SOCKET EMBEDMENT H2							
1000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"
2000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"
3000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-6"	4'-6"
4000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-6"	4'-6"	4′-6"	4'-6"	5′-0"
5000	3'-0"	12	#9	4'-0"	4'-6"	4'-6"	4'-6"	4'-6"	5′-0"	5′-0"	5′-0"
6000	3'-0"	12	#9	4′-6"	4′-6"	4′-6"	5′-0"	5′-0"	5′-6"	5′-6"	5′-6"
7000	3'-0"	12	#9	4'-6"	5′-0"	5′-0"	5′-6"	5′-6"	5′-6"	6'-0"	6′-0"
8000	3'-0"	16	#9	5′-0"	5′-0"	5′-6"	5′-6"	5′-6"	6'-0"	6'-0"	6′-6"
9000	3'-0"	16	#9	5′-0"	5′-6"	5′-6"	6'-0"	6'-0"	6'-0"	6′-6"	6′-6"
10,000	3'-0"	16	#9	5′-6"	5′-6"	6'-0"	6'-0"	6′-6"	6'-6"	7′-0"	7′-0"

						CASE	3 [5′ <u>≤</u> H1	< 10']			
DESIGN	"D"	"W"	BAR	20' SHAFT	22' SHAFT	24' SHAFT	26' SHAFT	28' SHAFT	30' SHAFT	32' SHAFT	34' SHAFT
(LBS)	*	QTY.	SIZE	ROCK SOCKET EMBEDMENT H2 **							
1000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"
2000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"
3000	3'-0"	12	#9	4'-0"	4′-0"	4'-0"	4'-0"	4′-0"	4′-0"	4'-0"	4'-0"
4000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4′ -6"	4′-6"	4′ -6"
5000	3'-0"	12	#9	4'-0"	4'-0"	4′-6"	4′-6"	4'-6"	4′ -6"	5′-0"	5′-0"
6000	3'-0"	18	#9	4′-6"	4′ -6"	4′ -6"	5′-0"	5′-0"	5′-0"	5′-6"	5′-6"
7000	3'-0"	18	#9	4′-6"	5′-0"	5′-0"	5′-6"	5′-6"	5′-6"	6′-0"	6′-0"
8000	3'-0"	18	#9	5′-0"	5′-0"	5′-6"	5′-6"	5′-6"	6′-0"	6′-0"	6'-6"
9000	3'-0"	18	#9	5′-6"	5′-6"	5′-6"	6′-0"	6′-0"	6′-0"	6′-6"	6'-6"
10,000	3'-0"	18	#9	5′-6"	5′-6"	6′-0"	6'-0"	6′-6"	6′ -6"	7′-0"	7′-0"

							CF 4 F114 \	4043			
						CA	SE 4 [H1 <u>≥</u>	10′]			
DESIGN			BAR	20' SHAFT	22' SHAFT	24' SHAFT	26' SHAFT	28' SHAFT	30' SHAFT	32' SHAFT	34' SHAFT
(LBS)	*	QTY.	SIZE	ROCK SOCKET EMBEDMENT H2 **							
1000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"
2000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"
3000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"
4000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"
5000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"
6000	3'-0"	12	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"
7000	3'-0"	18	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-6"	4'-6"
8000	3'-0"	18	#9	4'-0"	4'-0"	4'-0"	4'-0"	4'-6"	4' -6"	5′-0"	5′-0"
9000	3'-0"	18	#9	4'-0"	4'-0"	4'-6"	4'-6"	4'-6"	5′-0"	5′-0"	5′-6"
10,000	3'-0"	18	#9	4'-6"	4'-6"	4'-6"	5′-0"	5'-0"	5′-6"	5′-6"	5′-6"

- * INCREASE CAISSON DIAMETER BY 6" AS APPLICABLE IN ACCORDANCE WITH ROCK SOCKET NOTE 1 ON SHEET 4.
- ** SEE ROCK SOCKET NOTE 4 ON SHEET 4 FOR TOTAL "H" DEPTH REQUIREMENTS.

STRAIN POLE FOUNDATION NOTES:

- 1. FOUNDATION DESIGN IS BASED ON STANDARD STRUCTURAL LOADINGS SHOWN IN THE PUBLICATION 149 AND THE FOLLOWING DESIGN ASSUMPTIONS:
- a. A CABINET WITH A 4'-3" HEIGHT, 2'-6" WIDTH, 1'-10" DEPTH AND A DEAD LOAD OF 281 LBS. THE CENTROIDAL HEIGHT IS LOCATED 4'-6" FROM THE TOP OF THE FOUNDATION.
- b. A LUMINAIRE WITH A 15' ARM LENGTH AND THE FOLLOWING MOUNTING HEIGHTS FROM THE TOP OF ROADWAY:

30′
35′
40′
_


2. FOR DEFINITION OF CASES, SEE DRILLED SHAFT NOTES ON SHEET 3 AND DETAILS ON SHEET 4.


COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION BUREAU OF OPERATIONS

STANDARD

TRAFFIC SIGNAL SUPPORT - STRAIN POLE
FOUNDATION TYPE A

RECOMMENDED JUN 20, 2023	RECOMMENDED JUN 20, 2023	SHEET 6 OF 10
JXWI C		
CHIEF, TSMO ARTERIALS AND	CHIEF OF HIGHWAY SAFETY AND	TC-8801
PLANNING SECTION	TRAFFIC OPERATIONS DIVISION	





NOTE: A MINIMUM OF 6 'J' ANCHOR BOLTS IS REQUIRED FOR MAST ARM TRAFFIC SIGNAL SUPPORTS.

'J' ANCHOR BOLT


BY 6" FOR EACH 2-BOLT PAIR FOR 1 1/4" DIA. BOLTS AND BY 12" FOR EACH 2-BOLT PAIR FOR 2" DIA. BOLTS AND BY 12" FOR EACH 2-BOLT PAIR FOR 2" DIA. BOLTS. SEE L1, L2 AND L3 EMBEDMENT DEPTHS IN ANCHOR BOLT DESIGN TABLE.

ANCHOR BOLT DESIGN, MAST ARM

LILOT ABU				(DNE ARI	4			TWO ARMS *									
MAST ARM LENGTH	QTY.	BOLT DIA.	BEND DIA.	L1	L2	L3	в. с.	HOLE	BOLT DIA.	BEND DIA.	L1	L2	L3	в. с.	HOLE			
0 - 10'	6	1 3/4 "	171/2"	42 "	48"	54"	18"	2 "	1 3/4 "	171/2"	42 "	48"	54"	18"	2 "			
>10' - 15'	6	1 3/4 "	171/2"	42 "	48"	54"	18 "	2 "	1 3/4 "	171/2"	42 "	48"	54"	18"	2 "			
>15' - 20'	6	1 3/4 "	171/2"	42 "	48"	54"	18 "	2 "	1 3/4 "	171/2"	42 "	48"	54"	18"	2 "			
>20' - 25'	6	1 3/4 "	171/2"	42 "	48"	54"	18 "	2 "	1 3/4 "	171/2"	42 "	48"	54"	18 "	2 "			
>25' - 30'	6	1 3/4 "	171/2"	42 "	48"	54"	21"	2 "	1 3/4 "	171/2"	42 "	48"	54"	21"	2 "			
>30' - 35'	6	1 3/4 "	171/2"	42 "	48"	54"	21"	2 "	1 3/4 "	171/2"	42 "	48"	54"	21"	2 "			
>35' - 40'	6	2 "	22"	48 "	60"	72 "	24"	21/4"	2 "	22 "	48 "	60"	72 "	24"	21/4"			
>40' - 45'	6	2 "	22"	48 "	60"	72 "	24"	21/4"	2 "	22 "	48 "	60"	72 "		21/4"			
>45' - 50'	6	2 "	22"	48 "	60"	72 "	24"	21/4"	2 "	22 "	48 "	60"	72 "	24"	21/4"			
>50' - 60'	6	2 "	22"	48 "	60"	72 "	24"	21/4"	2 "	22 "	48 "	60"	72 "	24"	21/4"			

* TWO ARMS PERPENDICULAR TO EACH OTHER. ADDITIONAL STRUCTURAL ANALYSIS IS REQUIRED FOR TWO MAST ARMS AT ACUTE OR OBTUSE ANGLES TO EACH OTHER

B. C. = BOLT CIRCLE DIAMETER




21" DIA. BOLT CIRCLE

24" DIA. BOLT CIRCLE

PLAN

** DIAMETER IF CIRCULAR, OR SIDE IF SQUARE. CIRCULAR
FOUNDATIONS SHALL BE SQUARE FROM THE TOP TO A
POINT 6" BELOW THE GROUND LINE, IF SIDEWALK IS PRESENT



TYPE A FOUNDATION CASE 1 ALTERNATE

FOUNDATION FOR TRAFFIC SIGNAL SUPPORT, MAST ARM (SOIL CONDITION)

CASE 1 ALTERNATE									
MAST ARM	"D "		1	"W" BAR					
LENGTH		ONE ARM	TWO ARMS*	QTY.	SIZE				
0' - 10'	2'-6"	7′-6"	7'-6"	12	#9				
>10' - 15'	2'-6"	8'-0"	8'-6"	12	#9				
>15' - 20'	2'-6"	9'-0"	9'-0"	12	#9				
>20' - 25'	2'-6"	9'-0"	9'-6"	12	#9				
>25' - 30'	3′-0"	9'-6"	10'-0"	12	#9				
>30' - 35'	3′-0"	10'-0"	10'-6"	12	#9				
>35' - 40'	3'-0"	10'-6"	11'-0"	14	#9				
>40' - 45'	3'-0"	10'-6"	11'-6"	14	#9				
>45' - 50'	3'-0"	11'-0"	12'-0"	14	#9				
>50' - 60'	3'-0"	11'-6"	14	#9					

* TWO ARMS PERPENDICULAR TO EACH OTHER. ADDITIONAL STRUCTURAL ANALYSIS IS REQUIRED FOR TWO MAST ARMS AT ACUTE OR OBTUSE ANGLES TO EACH OTHER.

ALTERNATE TYPE A FOUNDATIONS AS SHOWN ON THIS SHEET REQUIRE APPROVAL BY THE BUREAU OF MAINTENANCE AND OPERATIONS.

MAST ARM FOUNDATION TYPE A ALTERNATE NOTES:

1. FOR ADDITIONAL DESIGN CRITERIA, NOTES AND DETAILS, SEE SHEETS 3 THROUGH 5.

COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION BURBAU OF OPERATIONS

STANDARD

TRAFFIC SIGNAL SUPPORT - MAST ARM FOUNDATION TYPE A ALTERNATE

	COMMENDED JUN 20, 2023	RECOMMENDED JUN 20, 2023	SHEET 7 OF 10
"	Pool A. The	RECOMMENDED SSX 25 9 2525	SHEET TOP TO
CHIE	EF, OSMO ARTERIALS AND	CHIEF OF HIGHWAY SAFETY AND	TC-8801
	NNING SECTION	TRAFFIC OPERATIONS DIVISION	

FOUNDATION FOR TRAFFIC SIGNAL SUPPORT, MAST ARM

MAST ARM		"W"	BAR	"L " BAR			S	-	S			
LENGTH	"D"	QTY.	SIZE	SIZE	ľ	ONE ARM	TWO ARMS*	Z	ONE ARM	TWO ARMS*		
0 - 10'	3'-0"	12	#9	#4	4'-0"	9'-6"	9'-6"	5′-0"	9'-6"	9′-6"		
>10' - 15'	3′-0"	12	#9	#4	4'-0"	10' -6"	10' -6"	5'-0"	10'-6"	10' -6"		
>15' - 20'	3'-0"	12	#9	#5	4'-0"	11'-6"	11'-6"	5′-6"	11'-6"	11'-6"		
>20' - 25'	3′-0"	12	#9	#6	4'-0"	12'-0"	12'-0"	6'-0"	12'-0"	12'-0"		
>25' - 30'	3′-0"	12	#9	#6	4'-6"	12'-6"	13'-0"	6'-6"	12'-6"	12'-6"		
>30' - 35'	3′-0"	12	#9	#7	4'-6"	13'-0"	13'-6"	7′-0"	13'-0"	13′-6"		
>35' - 40'	3′-6"	14	#9	#7	5′-0"	13'-6"	14'-0"	7′-0"	13'-0"	13′-6"		
>40' - 45'	3′-6"	14	#9	#7	5′-0"	13'-6"	14'-6"	7′-6"	13'-0"	13′-6"		
>45' - 50'	3′-6"	14	#9	#7	5′-6"	14'-0"	14'-6"	8'-0"	13'-0"	13′-6"		
>50' - 60'	3′-6"	14	#9	#8	5'-6"	14'-6"	16'-0"	8'-0"	13'-6"	14'-6"		

^{*} TWO ARMS PERPENDICULAR TO EACH OTHER. ADDITIONAL STRUCTURAL ANALYSIS IS REQUIRED FOR TWO MAST ARMS AT ACUTE OR OBTUSE ANGLES TO EACH OTHER.


FOUNDATION FOR TRAFFIC SIGNAL SUPPORT, STRAIN POLE


ſ		SHAFT LENGTH 20' - 24'												SI	HAFT LI	ENGTH 2	6' - 3	0′			SHAFT LENGTH 32' - 34'										
	DESIGN ENSION (LBS)	"D"	"W"	BAR	"L" BAR	Y	SL	s	Z	Sr	s	"D"	"W"	BAR	"L " BAR	Y	Sr	s	Z	SL	s	"D"	W	BAR	"L" BAR	Y	SL	S	Z	SL	S
	12207		QTY.	SIZE	SIZE								QTY.	SIZE	SIZE								QTY.	SIZE	SIZE						
	1000	3'-0"	12	#9	#4	4'-0"	9′-6	" 9'-0"	4'-0"	9'-6"	9'-0"	3'-0"	12	#9	#4	4'-0"	10' -6"	10' -6"	4'-0"	10' -6"	10' -0"	3'-0'	12	#9	#4	4'-0"	11'-0"	10'-6"	4'-0"	11'-0"	10'-6"
	2000	3'-0"	12	#9	#4	4'-0"	10' -6	" 10′ -6	4'-0"	10' -6"	10'-6"	3'-0"	12	#9	#5	4'-0"	12'-0"	12'-0"	4'-0"	12'-0"	11'-6"	3'-0'	12	#9	#5	4'-0"	12'-6"	12'-0"	4'-0"	12′-6"	12'-0"
	3000	3'-0"	12	#9	#5	4'-0"	11'-6	" 11′ -6	4'-0"	12'-0"	11'-6"	3'-0"	12	#9	#5	4'-0"	13'-0"	13'-0"	5'-0"	12' -6"	12'-0"	3'-0'	12	#9	#6	4'-0"	13'-6"	13'-0"	5'-0"	12′-6"	12'-6"
	4000	3'-0"	12	#9	#5	4'-0"	12'-6	" 12′ -0	5'-0"	12'-0"	12'-6"	3′-0"	12	#9	#6	4'-6"	14'-0"	14'-0"	6'-0"	12' -6"	12'-6"	3'-0'	12	#9	#6	4'-6"	14'-0"	14'-0"	6'-0"	13′-0"	13'-0"
	5000	3'-0"	12	#9	#6	4'-6"	13'-0	" 12′ -6	" 6' -0"	12'-0"	12'-6"	3′-0"	12	#9	#6	5'-0"	14'-6"	14'-6"	6'-6"	13' -0"	13'-0"	3'-0'	12	#9	#7	5'-0"	14'-6"	14'-6"	6' -6"	13′-6"	13'-0"
	6000	3'-0"	12	#9	#6	5'-0"	13'-0	" 13′ -0	6'-6"	12'-6"	12'-6"	3′-0"	12	#9	#7	5′-6"	14'-6"	14'-6"	7'-0"	13' -6"	13'-0"	3'-0'	12	#9	#7	5′-6"	14'-6"	14'-6"	7'-0"	14′-0"	13'-6"
	7000	3'-0"	12	#9	#7	5'-0"	13'-6	" 13′ -6	" 7′ -0"	13'-0"	13′-0"	3′-0"	12	#9	#7	6'-0"	15'-0"	15'-0"	8'-0"	13' -6"	13'-6"	3'-0'	16	#9	#8	6'-0"	15'-0"	15'-0"	8'-0"	14′-0"	13′-6"
	8000	3'-0"	12	#9	#7	5'-6"	14'-0	" 14' -0	" 7′ -6"	13'-0"	13'-0"	3′-0"	12	#9	#8	6' -6"	15'-6"	15'-6"	8'-6"	13' -6"	13' -6"	3'-0'	16	#9	#8	6' -6"	15'-6"	15'-6"	8'-6"	14′-0"	14'-0"
	9000	3'-0"	12	#9	#7	6'-0"	14'-0	" 14′ -0	8'-0"	13' -6"	13′-6"	3′-0"	16	#9	#8	7'-0"	15'-6"	15'-6"	9'-0"	14'-0"	13'-6"	3'-0'	16	#9	#9	7'-0"	15'-6"	15'-6"	9'-0"	14′-6"	14'-6"
[10,000	3'-0"	12	#9	#8	6'-6"	14'-6	" 14' -0	8'-6"	13' -6"	13′ -6"	3′-0"	16	#9	#9	7'-6"	15'-6"	15'-6"	10'-0"	14'-0"	14'-0"	3'-0'	16	#9	#9	7′ -6"	15'-6"	15'-6"	10'-0"	14′-6"	14'-6"


S^L = WITH LUMINAIRE

NOTES:

- 1. THE TYPE "B" FOUNDATION MAY BE AUTHORIZED FOR USE WHERE CONDITIONS PREVENT PLACING THE TYPE "A" FOUNDATION (AS SHOWN ON SHEET 4) TO ITS REQUIRED DEPTH.
- 2. FOR DESIGN CRITERIA SEE SHEET 3.
- 3. IN A SIDEWALK AND PAVED AREA, PLACE THE TOP OF FOUNDATION FLUSH WITH THE SURFACE OF THE ADJACENT PAVEMENT. IN UNPAVED AREAS TOP OF FOUNDATION TO BE AT LEAST 6" ABOVE TOP OF GROUND.
- 4. FOR GROUND ROD SIZE AND INSTALLATION DETAILS, SEE TC-8804.
- DISTANCE "F" AS REQUIRED TO AVOID PAVEMENT AND/OR CURB EXCAVATION.
- 6. SEE SHEET 4 FOR CLOSED TIE DETAIL.
- 7. SEE MAST ARM FOUNDATION NOTES 1 AND 2 ON SHEET 5.







SECTION G-G

TYPE B FOUNDATION

STRAIN POLE FOUNDATION NOTES:

- 1. FOUNDATION DESIGN IS BASED ON STANDARD STRUCTURAL LOADINGS SHOWN IN THE PUBLICATION 149 AND THE FOLLOWING DESIGN ASSUMPTIONS:
- d. A CABINET WITH A 4'-3" HEIGHT, 2'-6" WIDTH, 1'-10" DEPTH AND A DEAD LOAD OF 281 LBS. THE CENTROIDAL HEIGHT IS LOCATED 4'-6" FROM THE TOP OF THE FOUNDATION.
- 2. USE DIMENSION "S^L" IN THE TABLE WHEN A LUMINAIRE ARM OR A STUB IS SPECIFIED (STUB UTILIZED FOR AN OVERLAP SLIP JOINT FOR FUTURE LUMINAIRE ARM INSTALLATION). THE DESIGN ASSUMES A 15' LUMINAIRE ARM LENGTH AND THE FOLLOWING MOUNTING HEIGHTS FROM THE TOP OF ROADWAY:

LENGTH OF STRAIN POLE	LUMINAIRE MOUNTING HEIGHT "X"
20' , 22' , AND 24'	30′
26' , 28' AND 30'	35′
32' AND 34'	40′


** DIAMETER IF CIRCULAR, OR SIDE IF SQUARE. CIRCULAR FOUNDATIONS SHALL BE SQUARE FROM THE TOP TO A POINT 6" BELOW THE GROUND LINE, IF SIDEWALK IS PRESENT.


COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION BUREAU OF OPERATIONS

STANDARD

TRAFFIC SIGNAL SUPPORT FOUNDATION TYPE B

RECOMMENDED JUN 20, 2023	RECOMMENDED JUN 20, 2023	SHEET 8 OF 10
Property.	11	
CHIEF, TSMO ARTERIALS AND	CHIEF OF HIGHWAY SAFETY AND	TC-8801






* AS REQUIRED TO MEET THE DEPARTMENT'S "CRITERIA FOR THE DESIGN OF TRAFFIC SIGNAL SUPPORTS", PUBLICATION 149.

BASE PLATE

NOTE: A MINIMUM OF 6 ANCHOR BOLTS IS REQUIRED FOR MAST ARM AND STRAIN POLE TRAFFIC SIGNAL SUPPORTS (SHOWN). 4 ANCHOR BOLTS ARE REQUIRED FOR PEDESTAL POLE TRAFFIC SIGNAL SUPPORTS.

BASE PLATE AND CONNECTION PLATE THICKNESS

SHAFT OR COLUMN CONNECTION DIAMETER (IN)	PLATE THICKNESS MINIMUM, "T" (IN)
LESS THAN 6"	1"
6" TO 13"	2 "
GREATER THAN 13" BUT LESS THAN 19"	2 ½ "
GREATER THAN OR EQUAL TO 19"	3"




ELEVATION

SECTION B-B

MAST-ARM-TO-SHAFT CONNECTION DETAIL (RING-STIFFENED BUILT-UP BOX)


NOTE: SEAL ALL NON-WELDED JOINTS WITH SILICONE CAULK.



DETAIL B

(MAST ARM CONNECTION SHOWN, SHAFT CONNECTION TO BASE PLATE SIMILAR)


- 1. BACKING RING MUST BE FITTED/SIZED TO THE MAST ARM OR SHAFT AND CONTINUOUSLY FILLET WELDED TO THE CONNECTION PLATE OR BASE PLATE BEFORE THE FULL PENETRATION GROOVE WELD IS MADE. BACKING RING MUST BE FABRICATED AS A CONTINUOUS RING.
- 2. FOR MAST ARMS OR SHAFTS LESS THAN 18"0, THIS FILLET WELD IS NOT REQUIRED BUT SHOP IS TO APPLY SILICONE CAULKING TO THIS LOCATION AFTER POLE ASSEMBLY IS GALVANIZED.



OVERLAP SLIP JOINT DETAIL


(ALTERNATE METHOD TO PROVIDE LUMINAIRE)

(SEE NOTES 11 AND 12 ON SHEET 1)




MITIGATION DEVICE DETAIL


NOTE: INSTALL MITIGATION DEVICE WITHIN 5' OF MAST ARM TIP WHEN REQUIRED.



SECTION A-A



HAND HOLE DETAIL




DETAIL C


COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION BURBAU OF OPERATIONS

STANDARD


TRAFFIC SIGNAL SUPPORT
MISCELLANEOUS DETAILS

RECOMMENDED JUN 20, 2023	RECOMMENDED JUN 20, 2023	SHEET 10 OF 10
CHIEF, JSMO ARTERIALS AND PLANNING SECTION	CHIEF OF HIGHWAY SAFETY AND TRAFFIC OPERATIONS DIVISION	TC-8801





TRAFFIC SIGNAL SUPPORT-PEDESTAL



NOTES:


- 1. PROVIDE 24" LATERAL MINIMUM CLEARANCE. IF THERE IS NO CURB, MINIMUM CLEARANCE IS MEASURED FROM THE EDGE OF SHOULDER.
- 2. FOR DETAIL OF PEDESTAL FOUNDATION, SEE TC-8801.
- 3. PROVIDE 3" \times 5" HANDHOLE OPENING WITH A MINIMUM FRAME THICKNESS OF $\frac{3}{8}$ ".
- 4. DIMENSIONS "M" AND "N" ARE REFERENCED FROM TOP OF SIDEWALK.
 IF NO SIDEWALK IS PRESENT, DIMENSIONS ARE TO BE TAKEN FROM
 THE TOP OF PAVEMENT AT CENTER OF ROADWAY. PROVIDE DIMENSION
 "M" SUCH THAT VERTICAL CLEARANCE IS 8' MINIMUM TO 19' MAXIMUM
 FOR TRAFFIC SIGNAL HEADS. PROVIDE DIMENSION "N" SUCH THAT
 VERTICAL CLEARANCE IS 7' MINIMUM TO 10' MAXIMUM FOR PEDESTRIAN
 SIGNAL HEADS.
- 5. IN A PAVED AREA, PLACE THE TOP OF THE FOUNDATION FLUSH WITH THE SURFACE OF THE ADJACENT PAVEMENT. PROVIDE 1/2" PREMOLDED EXPANSION JOINT FILLER BETWEEN FOUNDATION AND ADJACENT PAVEMENT. SEE DETAIL C ON SHEET 10 OF TC-8801.
- 6. ALL ACCESSIBILITY FEATURES MUST BE COMPLIANT TO PENNDOT PUBLICATION 13M (DM-2), CHAPTER 6, PUBLICATION 72M (RC STANDARDS) CRITERIA AND PUBLICATION 149.
- PEDESTRIAN PUSHBUTTONS SHALL BE OF A TYPE APPROVED BY THE DEPARTMENT AND LISTED IN PUBLICATION 35 (BULLETIN 15).
- 8. PEDESTRIAN PUSHBUTTONS SHALL BE A MINIMUM OF 2" DIAMETER AND A FORCE PER ACTUATION THAT CANNOT EXCEED 5 LBS.
- 9. PROVIDE 4'-0" \times 4'-0" MINIMUM LANDING WITH 2.00% MAXIMUM SLOPE IN ALL DIRECTIONS WHERE PEDESTRIANS PERFORM 180° TURNING MANEUVERS.
- 10. FOR PEDESTRIAN PUSHBUTTON MOUNTING DETAILS, SEE SHEET 2.

COMMONWEALTH OF PENNSYLVANIA
DEPARTMENT OF TRANSPORTATION
BUREAU OF OPERATIONS


STANDARD

MISCELLANEOUS
TRAFFIC SIGNAL SUPPORT-PEDESTAL
PEDESTRIAN PUSHBUTTON

RECOMMENDED JUN 20, 2023	RECOMMENDED JUN 20, 2023	SHT. 1 OF 4
CHIEF, TSMO ARTERIALS AND PLANNING SECTION	CHIEF, HIGHWAY SAFETY AND TRAFFIC OPERATIONS DIVISION	TC-8803



TYPE C



NOTES:

- 1. REFER TO RC-67M FOR CURB RAMP AND SIDEWALK DETAILS.
- MOUNT PEDESTRIAN PUSHBUTTON BETWEEN 40" TO 44" ABOVE TOP OF SIDEWALK OR FINISHED GRADE TO THE EXPOSED CONDUIT AND LATERALLY 10" MAXIMUM FROM LEVEL LANDING.
- 3. ALL ACCESSIBILITY FEATURES MUST BE COMPLIANT TO PENNDOT PUBLICATION 13M (DM-2), CHAPTER 6, PUBLICATION 72M (RC STANDARDS) CRITERIA AND PUBLICATION 149.
- 4. IN A PAYED AREA, PLACE THE TOP OF THE FOUNDATION FLUSH WITH THE SURFACE OF THE ADJACENT PAVEMENT. PROVIDE ½" PREMOLDED EXPANSION JOINT FILLER BETWEEN FOUNDATION AND ADJACENT PAVEMENT. SEE DETAIL C ON SHEET 10 OF TC-8801.
- 5. PEDESTRIAN PUSHBUTTONS SHALL BE OF A TYPE APPROVED BY THE DEPARTMENT AND LISTED IN PUBLICATION 35 (BULLETIN 15).
- 6. PEDESTRIAN PUSHBUTTONS SHALL BE A MINIMUM OF 2" DIAMETER AND A FORCE PER ACTUATION THAT CANNOT EXCEED 5 LBS.
- 7. PEDESTRIAN PUSHBUTTON EXTENSION ARM TYPICALLY MEASURES UP TO 3".
 MAXIMUM LENGTH OF EXTENSION ARM TO BE 12". EXTENSION ARMS
 MEASURING GREATER THAN 12" REQUIRE DISTRICT APPROVAL PRIOR TO
 INSTALLATION.
- 8. INSTALL CONCRETE FOUNDATIONS IN ACCORDANCE WITH PUBLICATION 408 SECTION 951.2(b) AND 951.3(b).

COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION BUREAU OF OPERATIONS

STANDARD


MISCELLANEOUS PEDESTRIAN PUSHBUTTON MOUNTING DETAILS

RECOMMENDED JUN 20, 2023	RECOMMENDED JUN 20, 2023	SHT. 2 OF 4
CHIEF TSMO ARTERIALS AND	CHIEF, HIGHWAY SAFETY AND	TC-8803

PUSHBUTTON SIGN 2" ADA COMPLIANT PEDESTRIAN PUSHBUTTON (SEE NOTES 2 & 7) 3" EXPOSED GAL VANIZED CONDUIT PROVIDE FOUNDATION TYPE A FOR TRAFFIC SIGNAL SUPPORTPEDESTAL POLE. SEE TC-8801 FOR DETAILS.

TYPE D


TYPE E



VIEW A-A

CHEEKWALL

TYPE F



NOTES:


- 1. REFER TO RC-67M FOR CURB RAMP AND SIDEWALK DETAILS.
- 2. MOUNT PEDESTRIAN PUSHBUTTON BETWEEN 40" TO 44" ABOVE SIDEWALK OR FINISHED GRADE TO THE CENTER OF THE PUSHBUTTON AND 10" MAX LATERALLY FROM LANDING.
- 3. ALL ACCESSIBILITY FEATURES MUST BE COMPLIANT TO PENNDOT PUBLICATION 13M (DM-2), CHAPTER 6, PUBLICATION 72M (RC STANDARDS) CRITERIA AND PUBLICATION 149.
- 4. IN A PAYED AREA, PLACE THE TOP OF THE FOUNDATION FLUSH WITH THE SURFACE OF THE ADJACENT PAYEMENT. PROVIDE ½" PREMOLDED EXPANSION JOINT FILLER BETWEEN FOUNDATION AND ADJACENT PAYEMENT. SEE DETAIL C ON SHEET 10 OF TC-8801.
- 5. PEDESTRIAN PUSHBUTTONS SHALL BE OF A TYPE APPROVED BY THE DEPARTMENT AND LISTED IN PUBLICATION 35 (BULLETIN 15).
- PEDESTRIAN PUSHBUTTONS SHALL BE A MINIMUM OF 2" DIAMETER AND A FORCE PER ACTUATION THAT CANNOT EXCEED 5 LBS.
- 7. PEDESTRIAN PUSHBUTTON EXTENSION ARM IS TYPICALLY UP TO 3".
 MAXIMUM EXTENSION ARM OF 12". EXTENSION ARMS GREATER THAN 12"
 REQUIRE DISTRICT APPROVAL PRIOR TO INSTALLATION.
- 8. INSTALL CONCRETE FOUNDATIONS IN ACCORDANCE WITH PUBLICATION 408 SECTION 951.2(b) AND 951.3(b).


COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION BUREAU OF OPERATIONS


STANDARD

MISCELLANEOUS PEDESTRIAN PUSHBUTTON MOUNTING DETAILS


RECOMMENDED JUN 20, 2023	RECOMMENDED JUN 20, 2023	SHT. 3 OF 4
CHIEF TSMO ARTERIALS AND	CHIEF, HIGHWAY SAFETY AND	TC-8803








OF DIMENSI	ONS FOR
OR STEEL J	UNCTION BOX
JB-26	JB-27
12" MIN	12" MIN
12" MIN	18" MIN
12" MIN	24" MIN
	12" MIN 12" MIN



- WIDTH OF TRENCH AS REQUIRED TO PROPERLY INSTALL CONDUIT AND BACKFILL.
- RESTORE PAVEMENT AS SPECIFIED IN SECTION 954, PUBLICATION 408.
- BACKFILL WITH CLASS A CEMENT CONCRETE TO BOTTOM OF EXISTING SUBBASE.
- ⊕ BACKFILL WITH SUITABLE ON-SITE MATERIAL AS SPECIFIED IN SECTION 910.3(o), PUBLICATION 408.
 - O REPLACE SUBBASE IN KIND.
 - REPLACE IN KIND.


TRENCH AND BACKFILL



ELEVATION

B1

SECTION D-D




REINFORCED PLASTIC MORTAR OR


HIGH-DENSITY POLYMER CONCRETE

JUNCTION BOX, TYPE JB-26 TYPE JB-27 OR TYPE JB-30

TABLE OF DIMENSIONS FOR REINFORCED PLASTIC MORTAR OR HIGH-DENSITY POLYMER CONCRETE			
	JB-26	JB-27	JB-30
A2	11½" MIN	12" MIN	15½" MIN
B2	11½" MIN	18" MIN	28½" MIN
C2	12" MIN	24" MIN	24" MIN
D2	3∕4 " MIN	¾" MIN	2 "



JUNCTION BOX IN EARTH



SURFACE AND SIDEWALK

TYPICAL JUNCTION BOX INSTALLATION

NOTES:

- JUNCTION BOXES -- PROVIDE COVER WITH A NON-SLIP SURFACE AND A MINIMUM OF TWO CORROSION RESISTANT FASTENERS.
- JUNCTION BOXES -- USE JB-26, JB-27 AND JB-30 ONLY IN AREAS NOT SUBJECT TO VEHICULAR TRAFFIC.
- JUNCTION BOXES -- BOTTOM MAY BE OPEN OR CLOSED. IF CLOSED, PROVIDE A DRAIN HOLE 2" DIAMETER MINIMUM.
- 4. FOR DETAIL OF JUNCTION BOXES JB-1, JB-2, JB-11 AND JB-12, SEE STANDARD DRAWINGS, RC-81M AND RC-82M OF PENNDOT PUB. 72M.
- 5. GROUND EXPOSED METAL PARTS OF JUNCTION BOXES. USE GROUNDING LUGS. DO NOT CONNECT GROUND WIRE DIRECTLY TO LID.

COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION BUREAU OF OPERATIONS


STANDARD


ELECTRICAL DISTRIBUTION

Sph. a			
Skur Co	RECOMMENDED JUN 20, 2023	RECOMMENDED JUN 20, 2023	SHT. 2 OF 2
CHIEF / TSMO ARTERIALS AND CHIEF, HIGHWAY SAFETY AND TRAFFIC OPERATIONS DIVISION	CHIEF TEMO APTERIALS AND		TC-8804










CUT-AWAY VISOR

TUNNEL VISOR

VISOR DIME	NSION TABLE
Α	В
8 "	7" MIN
12"	9.5" MIN

*** THE VISOR SHALL HAVE A DOWNWARD TILT OF AT LEAST 3°.


VISOR TYPES FOR VEHICULAR SIGNAL HEAD




LOUVER FOR

VEHICULAR SIGNAL HEAD

(DO NOT USE WITH CUT-AWAY VISOR)





CUT-AWAY VISOR


TUNNEL VISOR


LOUVER VISOR (FOR PEDESTRIAN SIGNAL HEAD ONLY)


VISOR TYPES FOR PEDESTRIAN SIGNAL HEAD AND LANE-USE TRAFFIC CONTROL SIGNAL HEAD





ONE-SECTION














ONE-SECTION

TWO OR THREE SECTIONS

* NOMINAL. ACTUAL DIMENSIONS ARE AS REQUIRED TO PROVIDE SYMBOLS IN ACCORDANCE WITH ITE STANDARD FOR "LANE-USE TRAFFIC CONTROL SIGNAL HEADS" AND CURRENT ADDITION OF MUTCD.

BACKPLATE FOR VEHICULAR SIGNAL HEAD *

* BACKPLATE CONFORMING TO PUBLICATION 408 SECTION 955.2(B) 3 SHALL BE ONE PIECE ALUMINUM

LANE-USE TRAFFIC CONTROL SIGNAL HEAD

TWO-SECTIONS

TYPE A (COUNTDOWN) *

TWO-SECTIONS

TYPE B (SYMBOL) **

TYPE	DIMENSION A
Α	6" *
В	6"**

- * COUNTDOWN PEDESTRIAN SIGNALS SHALL CONSIST OF PORTLAND ORANGE NUMBERS THAT ARE AT LEAST 6"
 IN HEIGHT. FOR CROSSWALKS WHERE THE PEDESTRIAN ENTERS THE CROSSWALK MORE THAN 100' FROM THE COUNTDOWN
 PEDESTRIAN SIGNAL DISPLAY, THE NUMBERS SHOULD BE AT LEAST 9" IN HEIGHT.
- ** FOR CROSSWALKS WHERE THE PEDESTRIAN ENTERS THE CROSSWALK MORE THAN 100' FROM THE PEDESTRIAN SIGNAL HEAD INDICATIONS, DIMENSION "A" SHOULD BE AT LEAST 9" HIGH.

NOTE:

PEDESTRIAN SIGNALS MAY INCLUDE A COUNTDOWN TIMER THAT OPERATES DURING THE "FLASHING UPRAISED HAND" PHASE.


COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION BUREAU OF OPERATIONS


STANDARD

SIGNAL HEADS

RECOMMENDED JUN 20, 2023	RECOMMENDED JUN 20, 2023	SHT. 1 OF 1
CHIEF, TSMO ARTERIALS AND PLANNING SECTION	CHIÉF, HIGHWAY SAFETY AND TRAFFIC OPERATIONS DIVISION	TC-8805

PEDESTRIAN SIGNAL HEAD







ALTERNATE C SPLICE WILL BE MADE ELECTRICALLY SECURE WITH INSULATED COMPRESSION CONNECTORS THEN COVERED WITH A SPLICING KIT THAT IS MOISTURE-PROOF, SPLICE ENCAPSULATING (INCLUDING CABLE JACKET), AND DESIGNED FOR INSULATING AND SPLICING ELECTRIC CABLE; OR A RE-ENTERABLE SPLICE KIT AS SPECIFIED IN SEC. 956.2(b) 4, PUBLICATION 408.

ALTERNATE C

ALTERNATE B ALTERNATE A



SECTION E-E TYPICAL SENSOR INSTALLATION - MAGNETIC DETECTOR



TYPICAL SENSOR INSTALLATION - MAGNETOMETER DETECTOR

COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION BUREAU OF OPERATIONS

STANDARD

DETECTORS

	RECOMMENDED JUN 20, 2023	RECOMMENDED JUN 20, 2023	SHT. 2 OF 2
	CHIEF, TSMO ARTERIALS AND	CHTÉF, HIGHWAY SAFETY AND	TC-8806
- 1	DI ANNING SECTION	TDACETO ODEDATIONS DIVISION	100000